





LQF-510-02

Test report: H13-30001

Page 1 of 7

TEST REPORT

Project No.: *H13-30001*

Test Report For: Composite shelter

Manufacturer

: ARVIN SANAT BASPAR

Model

: SLT 8040

Serial number

: SMC1100

Tested according to: Client request

Applicant: ARVIN SANAT BASPAR Co.

No. Pages

Issue date

02-May-2017

Prepared: Test Engineer

A. Takzare

Verified: Head of HV/ATEX Lab

S. M. Dezfulian

Approved:

Vice President of CEO

S. M. Mirsadri

Engineering Deputy of Test and Inspection

Prof. B. Vahid

This test report does not include an assessment of the manufacturer's production. Conformity of the production with tested sample is not the responsibility of EPIL.

Technical Department 150 IEC 17025

Accre This report should not be reproduced in extracts without written approval by EPIL.

Test results pertain to the tested sample only.

Not Valid Without Lab Stamp.

www.eepil.com







Test report : H13-30001

Page 2 of 7

LQF-510-02

CONTENTS

		Page
1	GENERAL INFORMATION	3
1.1	Product Information	3
1.2	Client Information	3
1.3	Test Performed	3
1.4	Test Results and Descriptions	3
2	PERFORMANCE AND RESULTS OF TESTS	4
2.1	Dielectric Test	4
3	FIGURES	6



This report should not be reproduced in extracts without written approval by EPIL. Test results pertain to the tested sample only. Not Valid Without Lab Stamp.







LQF-510-02

Test report : H13-30001

Page 3 of 7

: SMC1100

1. GENERAL INFORMATION

1.1. Product Information

Equipment under test : Composite shelter

Manufacturer : ARVIN SANAT BASPAR

Model : SLT 8040

Year of manufacture : 1396

Standard : Client request

1.2. Client Information

Serial number

Applicant : ARVIN SANAT BASPAR Co.

Telephone : +98 2156417042

Fax : +98 2156416982

1.3. Tests Performed

Dielectric test

1.4. Test Results and Descriptions:

See page 4.



This report should not be reproduced in extracts without written approval by EPIL.

Test results pertain to the tested sample only.

Not Valid Without Lab Stamp.





LQF-510-02

Energy & Power Industries Laboratories Co.(J.S.)

Test report: H13-30001

Page 4 of 7

2. PERFORMANCE AND RESULTS OF TESTS

2.1 Dielectric Test

2.1.1 Test data

Equipment under test (EUT) : Composite shelter

: ARVIN SANAT BASPAR Manufacturer

Location : E.P.I.L.

Date : 01-May-2017

Engineer of EPIL : Mrs. Takzare

Normative document : Client request

2.1.2 Ambient conditions

Ambient Temperature : 25.8 °C

Relative Humidity : 29.1 %

: 865 hPa Pressure

2.1.3 Performance and result of test

According to clause 10.9.4 of IEC 61439-1:2011 for assemblies with enclosures made of insulating material, a dielectric test shall be carried out by applying an a.c. test voltage between a metal foil laid on the outside of the enclosure over openings and joints, and the interconnected live and exposed conductive parts within the assembly located next to the openings and joints.

In case of the equipment under test, the enclosure is empty without any assembled devices. Thus, according to client request, the minimum possible distance between metal foil laid on the outside of enclosure over openings and prospective joints and live and exposed conductive parts is considered in the test using metal foil sheets on openings and joints inside of the enclosure. The inside foil acts as prospective conductive parts in the most unfavorable condition i.e. closest position to the enclosure walls. In normal condition, the assemblies are always placed in farther distance from enclosure walls, which leads to higher values of breakdown and withstand voltage values.

The test was carried out by applying an alternating voltage at power frequency (50 Hz) between outside and inside metal foils (see figure 2).

Lelle C Technical Department ISO IEC 17025

This report should not be reproduced in extracts without written approval by EPIL. Test results pertain to the tested sample only.

Not Valid Without Lab Stamp.







LQF-510-02


Test report: H13-30001

Page 5 of 7

For breakdown voltage test, the applied voltage is gradually increased from zero until breakdown is occurred. Power frequency withstand voltage test is carried out by applying 4 kV between metal foils at inside and outside of the enclosure and maintained for 60 second. Table 1 shows the results of the test.

Table 1: Results of the breakdown and withstand voltage tests

Breakdowr	n voltage test	Power frequency withstand voltage test	
Breakdown voltage (kV)	Rate of voltage rise (V/sec)	Applied voltage (kV)	Time (sec)
4.48	500	4	60



This report should not be reproduced in extracts without written approval by EPIL.

Test results pertain to the tested sample only.

Not Valid Without Lab Stamp.







LQF-510-02

Test report : H13-30001

Page 6 of 7

3. FIGURES



Figure 1: EUT nameplate



Figure 2: Metal foil that used for dielectric test

Technical Department
ISO IEC 17025
Accredited Lab

This report should not be reproduced in extracts without written approval by EPIL.

Test results pertain to the tested sample only.

Not Valid Without Lab Stamp.

info@eepil.com

www.eepil.com







LQF-510-02

Test report: H13-30001

Page 7 of 7



Figure 3: EUT under dielectric test

E.F. I. L. **Technical** Department ISO IEC 17025 Accredited Lab

> This report should not be reproduced in extracts without written approval by EPIL. Test results pertain to the tested sample only. Not Valid Without Lab Stamp.

www.eepil.com

info@eepil.com